



Water Service Notes:

- DMU shall inspect water service and curb stop assembly for damage.
- Installer shall be responsible to protect curb stop assembly from damage during construction and site work.
- Tracer wire shall be constructed of 12 gauge copper with steel core with blue jacket as manufactured by Copperhead Industries or equal.
- Contractor shall secure tracer wire to pipe via tape or nylon ties.
- Contractor shall provide a 24" tail of locating wire securely fastened at both ends for future locating work.

